

Progress on the LCLS-II and the High Energy Upgrade LCLS-II-HE

Tor Raubenheimer

Future Light Sources Workshop 2018, March 5-9, 2018



Outline

- LCLS-II Overview
- LCLS-II-HE Concept
- Performance and Operating Modes

New SCRF linac and injector in 1st km of SLAC linac tunnel And LCLS-II Upgrade (1st light 2020)

2-km point

Injector

Existing Linac (1 km)-(with modifications)

Electron Transfer Line (340 m)

Undulators (130 m)

Near Experiment Hall

Fransport Line

(200 m)

Far Experiment Hall

LCLS-II X-ray Coverage Using SASE and Self-Seeding



LCLS-II Accelerator Layout New Superconducting Linac → LCLS Undulator Hall

- Two sources: MHz rate SCRF linac and 120 Hz Cu LCLS-I linac
- Hard and Soft X-ray undulators can operate simultaneously in any mode
- SCRF beam destination controlled with fast (μs) magnetic deflector

Undulator	SC Linac (up to 1 MHz)	Cu Linac (up to 120Hz)
Soft X-ray	0.20 - 1.3 keV with >> 20 Watts	
Hard X-ray	1.0 - 5.0 keV with > 20 Watts	1 - 25 keV with mJ-class X-ray pulses



Future Light Sources Workshop, March 5-9, 2018

LCLS-II Injector Status

- Laser temporarily installed and running at SSRL
- Gun delivered to SLAC
- Early injector commissioning starts spring 2018



Future Light Sources Workshop, March 5-9, 2018



186 MHz CW RF gun



Injector low energy beamline

LCLS-II Cryomodule Based on ILC and XFEL 1.3 GHz Cryomodules



CM to be fabricated at FNAL and JLab; Prototypes have been assembled and tested in 2017. Installation 2018.

LCLS-II Cryomodule Status

37 CMs to be installed

First 1.3 GHz CM at SLAC but have had vacuum problems





Cryoplant Building – Two 4-kW plants (2K)

- Building nearly complete
- Warm compressor
 installation started





Warm Helium Compressor Installed



Variable Gap Hybrid Undulators

Will install two new undulators in Hall

Variable gap undulators used in LCLS-II to provide greater wavelength tuning flexibility: standard vertical gap for SXR and a horizontal gap Vertically Polarized Undulator for HXR.







Future Light Sources Workshop, March 5-9, 2018

LCLS-II Undulator Layout Replace Existing LCLS Undulator with HXR and add SXR



LCLS-II-HE Goals Build on LCLS-II Performance Goals



- 1. Hard X-rays at 1 13 keV with the possibility of approaching 20 keV
- Soft X-rays at 0.2 1.3 keV or 1 5 keV at the same time as the production of hard X-rays
- 3. Hard X-ray (as well as soft X-ray) self-seeding at MHz-rates
- 4. The hard X-ray beamlines and instruments will be upgraded to maximize the science from the MHz-rate high energy FEL beams
- 5. Hard X-ray experimental hall (FEH) will be modified to incorporate an additional experimental instrument
- 6. The performance of LCLS and LCLS-II operational modes and techniques will not be negatively impacted by the LCLS-II-HE upgrade

Future Light Sources Workshop, March 5-9, 2018



Future Light Sources Workshop, March 5-9, 2018



























LCLS-II-HE Accelerator Configuration



Add linac section L4 and increase gradient to reach 8 GeV
Extract 3-4 GeV beam to maintain soft X-ray program
Keep Sector-10 access clear for access and maintenance
Fit 20 new cryomodules before S10 access including LE extraction
Utilize LCLS-II injector and bunch compressor configuration
No layout changes upstream of L3
Add 2nd HXR Self-seeding for high rate operation

LCLS-II Cavity Performance



- RI/TD cavities in VT have average Q₀ of 3.4 x 10¹⁰ with ave. gradient ~23 MV/m (including 24 MV/m admin. testing limit)
- Working on translation into CM but others have seen ~15% gradient reduction, i.e. >19 MV/m, consistent with 1st LCLS-II CM
- More knowledge with ~20 CM tests within the next year

 Q_0 consistently exceeds $3x10^{10}$ with many cavities being much higher (3.4x10¹⁰ average) BUT more than 50% of cavities quench at or below 24 MV/m in VT (LCLS-II-HE spec is 24.5 MV/m)

→ Tweak N₂ doping to 8 trade Q₀ for gradient $\begin{bmatrix} I \\ I \\ I \\ I \end{bmatrix}$ ⁶



Future Light Sources Workshop, March 5-9, 2018

Achieving 8 GeV with LCLS-II Infrastructure 1 km linac tunnel and 8 kW 2K cooling



Heat load is minimized at ~8 MV/m with 2+ km linac length but extra length will significantly increase cost

Future Light Sources Workshop, March 5-9, 2018

LCLS-II SRF Linac Modifications for LCLS-II-HE



- No layout changes up through middle of L3
- Move 7 LCLS-II CM from L3 40-meter downstream to create break for Low Energy Extraction (LEX) break
- Extract 3.8 GeV beam to 2nd bypass line in ~40-m space
- Add 20 new LCLS-II-HE CM in L4
- Use CP1 to cool L0 L3 and CP2 to cool L4

Future Light Sources Workshop, March 5-9, 2018

LCLS-II-HE RF Power Upgrades

- Upgrade ~100 SSAs to 5 kW for operation at 18 MV/m ave.
- Install 160 new 7 kW SSAs for HE cryomodules at 20.8 MV/m



Future Light Sources Workshop, March 5-9, 2018

Gradient and Field Emission Risk Mitigation

Believe that LCLS-II gradient of 18 MV/m is likely reasonable but LCLS-II-HE gradient of 21 MV/m has risk – *will know more in a year*

- Trade gradient in the LCLS-II-HE cryomodules for the LCLS-II cryomodules → small increase in cost due to additional RF source upgrades
- The HXU period shortened to ~22 mm allowing for a *lower final* beam energy and an average gradient of 18 MV/m
 → reduces long wavelength performance
- **3**. The injector emittance and linac brightness could be improved allowing for *lower final beam energy* and 18 MV/m
- 4. The SRF linac at 18 MV/m could be lengthened by 3 or more cryomodules → most costly (~20M\$) but maintains capability

LCLS-II High Energy Upgrade LCLS-II extension to go from 5 keV → 12.8 keV or more

Left space in the LCLS-II for additional cryomodules

→ Add 20 additional cryomodules and 2nd bypass Three independent sources: CuRF 2-15 GeV, 120 Hz; LCLS-II: 3-4 GeV, 31 μ A; LCLS-II-HE: 3-8 GeV, 31 μ A



LCLS-II/LCLS-II-HE Accelerator Parameters

SCRF-Linac Parameters	LCLS-II	LCLS-II-HE	Unit
Final electron energy	3.3 - 4.0	3.3 - 8.0	GeV
Electron energy at L3/L4 extraction point	-	3.3 - 4.0	GeV
Electron Bunch Charge	0.01-0.30	0.01-0.30	nC
Max. bunch repetition rate	929	929	kHz
Average electron beam power in L2-L4	<0.25	<0.25	MW
Average electron power in BSY	<0.25	<0.375	MW
Max. avg. electron current in LO-L3	62	62	μA
Max. avg. electron current in L4		31	μA
Max. avg. electron current in Low Energy Extraction line		31	μA
Total Number of 1.3-GHz Cryomodules	35	55	-
Total Number of 3.9-GHz Cryomodules	2	2	-
Installed 1.3 GHz RF Voltage	4.65	8.64	GeV
Active SCRF accelerator length	296	462	m
1.3 GHz Cryomodules in L0, L1, L2, L3	1, 2, 12, 20	1, 2, 12, 13	-
1.3 GHz Cryomodules in L4		27	-
RF Overhead (spare cavities)	6.1	4.1	%
Mean RF Gradient in powered cavities: L0-L1	< 16.0	< 16.0	MV/m
Mean RF Gradient in powered cavities: L2-L3	< 16.0	18.0	MV/m
Mean RF Gradient in powered LCLS-II cavities: L4		18.0	MV/m
Mean RF Gradient in powered LCLS-II-HE cavities: L4		20.8	MV/m
Installed 2K cryo-capability	8.0	8.0	kW
Expected heat load at max energy: L0-L3	3.7	3.5	kW
Expected heat load at max energy: L4	-	3.8	kW

LCLS-II-HE X-ray Performance



Analytic Estimate of Power at the 3rd Harmonic Without post-saturation taper



Start-2-End Simulation Results

Examples at 8 and 13 keV

	Fundamental Energy	8 keV	13 keV	Unit s
	Maximum Repetition Rate	929 (300)	929 (300)	kHz
	FW Pulse Duration	30 (105)	30 (102)	fs
	Total energy/pulse	235 (625)	108 (57)	μJ
	Source point relative to end of undulator	25 (19)	24 (21)	m
Firs	t Harmonic			
	Photons per FEL pulse	0.18 (0.49)	0.05 (0.028)	10 ¹²
	Relative FWHM Bandwidth	0.05 (0.09)	0.06(0.1)	%
	FWHM Source Size	36 (37)	26 (22)	μm
	FWHM Source Divergence	2.4 (2.0)	1.8 (1.8)	μ rad
Thir	d Harmonic			
	Photons per FEL pulse	0.15 (0.29)	0.016 (0.005)	10 ¹⁰
	Relative FWHM Bandwidth	0.05 (0.09)	0.06 (0.1)	%
	FWHM Source Size	<36 (<37)	<26 (<22)	μm
	FWHM Source Divergence	<2.4 (<2.0)	<1.8 (<1.8)	μ rad



Future Light Sources Workshop, March 5-9, 2018

LCLS-II-HE Operating Modes

Spreader kickers allow flexible bunch patterns to SXR and HXR

















Photon Energy Upgrade Options



LCLS-II-HE X-ray Pulse Energy

Expected performance, including post-saturation taper, with improved injector is illustrated in green



Brightness of LCLS-II-HE will exceed 10²⁵ at 12.8 keV and extend out to >20 keV with additional injector improvements



LCLS-II-HE Conceptual Design Report



Linac Coherent Light Source II High Energy Upgrade (LCLS-II-HE) Project

LCLS-II-HE Conceptual Design Report

LCLSIIHE-1.1-DR-0001-R0

>30 SLAC staff members contributed to the CDR.

Future Light Sources Workshop, March 5-9, 2018

Chapter	Title
	Preface
	Introduction
1	Project Summary, Background, & Mission Need
2	Scientific Opportunities
3	Project Overview
4	Accelerator Parameters & FEL Performance
5	LCLS-II-HE FEL Layout
6	SRF Linac Systems
7	Electron Transport
8	Photon Transport and Diagnostics
9	Experimental Instruments
10	Controls and Safety Systems
11	Data Systems
12	Infrastructure and Facilities
13	Radialogical Considerations
14	Environment, Safety, Health
15	Upgrade Opportunities
App. A	LCLS-II-HE Key Parameters

https://slacspace.slac.stanford.edu/sites/reviews/lclsiihe/cdr_ch/LCLS-II-HE CDR Sept 24.pdf

External CDR Review – Oct. 27, 2017

Subcommittee	System	Name	email	SLAC POC	email
SC1	Accelerator Systems	Willeke, Ferdinand	willeke@bnl.gov		<u>tor@slac.stanford.edu</u>
		Temnykh, Sasha	abt6@cornell.edu		
		Price, Jeremy	pricejp@ornl.gov	Tor Raubenheimer	
		Lilje, Lutz	<u>lutz.lilje@desy.de</u>		
		Geloni, Gianluca	gianluca.aldo.geloni@xfel.eu		
		Ferreira, Marcelo	marcelo.ferreira@esss.se		
	Cryomodule	Olivier Napoloy	<u>napoly@fnal.gov</u>		aburrill@slac.stanford.edu
SC2		Joel Fuerst	fuerst@aps.anl.gov	Andrew Burrill	
		Liepe, Matthias	mul2@cornell.edu		
	Cavities	Alexander Romanenko	aroman@fnal.gov		aburrill@slac.stanford.edu
SC3		Liepe, Matthias	mul2@cornell.edu	Andrew Burrill	
		Jacek Sekutowicz	jacek.sekutowicz@desy.de		
804	DE	Champion, Mark	<u>championms@ornl.gov</u>	Chris Adolphsen	<u>star@slac.stanford.edu</u>
504		Jacek Sekutowicz	jacek.sekutowicz@desy.de		
	Cryogenics	Arnold, Phillipp	philipp.arnold@esss.se	Andrew Burrill	aburrill@slac.stanford.edu
SC5		Than, Roberto	<u>vthan@bnl.gov</u>		
		Joel Furst	fuerst@aps.anl.gov		
	Photon Systems	Gruenert, Jan	jan.gruenert@xfel.eu		<u>dmfritz@slac.stanford.edu</u>
		Assoufid, Lahsen	assoufid@aps.anl.gov		
SC6		Berman, Lonny	<u>berman@bnl.gov</u>	David Fritz	
		Schmidt, Thomas	thomas.schmidt@psi.ch_		
		Sinn, Harald	<u>harald.sinn@xfel.eu</u>		
	Controls	Maclean, John	<u>ifm@aps.anl.gov</u>		<u>hamid@slac.stanford.edu</u>
SC7		Crofford, Mark	<u>croffordmt@ornl.gov</u>	Hamid Shoaee	
		Fries, Greg	<u>gfries@bnl.gov</u>	Hanna Shouce	
		Ganetis, George	<u>ganetis@bnl.gov</u>		
SC8	Infrastructure and safety	Bull, Brad	bull@frib.msu.edu		
		Fallier, Martin	<u>fallier@bnl.gov</u>		
		Floyd, Jim	JGFloyd@lbl.gov	Jess Albino	albino@slac.stanford.edu
		Herman, Gregg	greg.herman@pnnl.gov_		
		Rowland, Douglas (Greg)	rowlanddg@ornl.gov_		

Summary

- LCLS-II on track to deliver MHz-rate FEL X-ray's from 0.2 to 5 keV with commissioning in 2020
- LCLS-II-HE uses capacity designed into LCLS-II to double electron beam energy and increase spectral reach >12.8 keV
- R&D program to electron beam brightness will further increase spectral range to ~20 keV
- Capabilities developed at LCLS should be available at LCLS-II and LCLS-II-HE

Evolution of superconducting linac layouts



Future Light Sources Workshop, March 5-9, 2018